SIRA TOWN MUNICIPALITY.

Dated 2nd February 1929.

1. Notice is hereby given that sealed tenders will be received at the office of the President, Town Municipal Council, Sira, up to 25th February 1929, for removing the old existing mutton stall and constructing a new one at Sira Town. An approximate estimate of the quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the office of the President, Town Municipal Council, Sira, between the hours of 11 A.M. and 5 P.M. or on application to the office.

3. Tenders should be presented on the forms which may be obtained from the office of the President, Town Municipal Council, Sira. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for removing the old existing mutton stalls and constructing a new one at Sira Town" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Town Municipal Council, Sira, which do not bind itself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the office of the President, Town Municipal Council, Sira, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of the quantities for removing the old existing mutton stall and constructing a new one at Sira Town. (Constructing one of block of stalls.)

Serial No.	Details of work	Per	Quantity
1	Earthwork excavation for foundation	C.yds.	11
2	Chunam mortar concrete foundation	C.ft.	81
3	Rough stone in mud foundation	"	92
4	Burnt brick in clay superstructure	"	717
5	Burnt stone uprights 6" thick, one line dressing, cutting grooves on top and fixing, etc., complete.	S.ft.	63
6	Burnt stone bed slabs 6" thick undressed of uprights ...	"	27
7	M. S. M. Rail bressummer	R.ft.	60
8	Teakwood work wrought and put up with wood oiling ...	C.ft.	16·73
9	Roofing with 1st class Mangalore tiles on teak reepers 2"×1" complete.	Sqr.	4·80
10	Chunam borders over roof	R.ft.	32
11	Teakwood ventilators with expanded metal filling	S.ft.	51
12	Flooring with burnt stone slabs on 3" burnt stone jelly in chunam mortar concrete bed with cement pointing, complete.	Sqr.	2·95
13	Chunam plastering	Sqr.	8·31
14	Whitewashing two coats as per plastering	"	8·31
15	Filling earth for pial of stall	C.yds.	15
16	Teakwood eave board with painting	R.ft.	30
17	Chunam pointing to basement	Sqr.	73
	... ... Total of one Block	Lump sum	

OFFICE OF THE PRESIDENT, DISTRICT BOARD, HASSAN.

Notice dated 4th February 1929.

The public are hereby informed that a cattle show will be held at Gorur, in the Hassan-Taluk from the 17th to the 18th February 1929, in connection with the car festival of Sri Yoganarasimhaswami at the place, under the auspices of the District Board.

For further particulars apply to the President, District Board, Hassan.

KENI MAHADEVAPPA,
For *President.*